No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
13	Teakwood wrought and put up including 2 coats of wood oiling	C.ft.	4 8 0	35·79	161
14	Burnt brick in lime mortar entablature wall 1′ high, 1½′ thick as per design including lime mortar, plastering and colour-washing	R.ft.	0 10 0	49	31
15	Tata's tested R. S. beams including hoisting and fixing and 2 coats of anticorrosive paint ..	Cwt.	9 8 0	15	143
16	Roofing with R.C.C. (1 : 2 : 4) designed to carry a total load of 1½ cwts. per sqr., for a clear span of 7 to 9′ including smooth lime mortar plastering for ceiling with coving and 3″ of surki concrete 2 courses of flat tiles laid in lime mortar on top and lime plastered over	Sqr.	60 0 0	16·60	996
17	Roofing with 1st class Mangalore tiles on teak reepers including tying the end tiles to double reepers with G.I. wire	,,	18 0 0	6·03	108
18	Providing and fixing 1st class Mangalore ridge tiles set in lime mortar and cement pointed	R.ft.	0 7 0	68	30
19	Flooring with 1½″ thick cement concrete on 3″ lime concrete and 9″ sand filled boulders the top finished with ¼″ thick coloured cement mortar with neat cut lines as per design ..	Sqr.	23 0 0	14·93	343
20	Flooring with 1½″ thick Cuddapa slabs on 3″ lime concrete and cement pointed including cutting lines	,,	18 0 0	1·53	28
21	Burnt brick in lime mortar parapet wall of modern type 1½′ height 9″ thick with blocking course and coping as per design including lime mortar plastering and color washing ..	R.ft.	0 12 0	281	211
22	Lime mortar plastering 2 coats over brick wall..	Sqr.	3 0 0	78·47	235
23	Colour washing 2 coats outside and white-washing 2 coats inside	,,	0 4 0	78·47	20
24	Cement pointing basement as per raking joints..	Sqr.	3 0 0	3·58	F.
25	Levelling and forming ground	L. S.	..	..	50
26	Electric fittings	,,	..	..	200
27	Water-supply connections	,,	..	..	100
28	Sanitary fittings	,,	..	..	200
29	Constructing Brindavan pestle and mortar ..	,,	..	..	30
30	Providing sink and oven with chimney in kitchen and bath	,,	..	..	30
31	Providing zinc rain water spouts	,,	..	..	14
32	Do valley sheets	,,	..	..	15
33	Constructing W.C. and wall enclosing quadrangle	,,	..	..	150
34	Providing planks and stone benches in store and kitchen	,,	..	..	25
35	Constructing a garage and additional bath	,,	..	..	1,031
36	Constructing a well	,,	..	..	1,000
37	Unforeseen charges	,,	..	..	50
38	Petty supervision	,,	..	..	140

B. R. GARUDACHAR,
Sanitary Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE COMPILER, *MYSORE GAZETTE.*

ERRATUM.

For the existing para 6 of tender Notification of the Executive Engineer, Mysore Division, published on page 1038 of Part VI of the *Mysore Gazette*, dated 1st July 1937, *substitute* the following :

"6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited."

B. SREENIVASA IYENGAR,
Compiler.